CITY OF PLAINVIEW

COMMERCIAL INSPECTION PROCEDURES

(To request inspections, please call: (806) 296-1100)

STRUCTURAL PROCEDURES

FOOTING:

- 1. Plans and permit on site, survey stakes visible
- 2. Setbacks as required (see plans)
- 3. Width and depth, thickness of footing
- 4. Steel in place and tied properly
- 5. Fireplace footing, inside or outside
- 6. Footing free of debris, water, and dirt

SLAB:

- 1. Plans and permit on site
- 2. Slab thickness
- 3. All steel in place and tied properly
- 4. Slab proper height above curb
- 5. All bearing wall footings in place, as per plans
- 6. All cooper tubing wrapped properly
- 7. Return air ducts cleaned out properly
- 8. Inside fireplace footing dug with steel in place
- 9. Make sure slab is ready prior to calling in inspection

FRAMING:

- 1. Outside sheathing installed and nailed
- 2. Roofing material, overhangs, and decking
- 3. Studs nailed properly and graded
- 4. Bracing for roof and wind installed
- 5. Sole plates fastened down properly
- 6. Joists, rafters, grades, and spans.
- 7. Engineered trusses in place correctly
- 8. Walkways for mechanical units in attic
- 9. Metal joist hangers and hurricane ties installed
- 10. Bath vents and elbows
- 11. Window sizes
- 12. Beams construction and spans
- 13. Bearing for beams and girder trusses
- 14. Fireplace framing
- 15. Headers over windows and doors
- 16. Stairs, rise and run, guardrails, and handrails
- 17. Firewalls, draftstops, fire blocking
- 18. Lighting and attic access

PLUMBING/MECHANICAL PROCEDURES

- 1. Obtain Plumbing and Mechanical Permit
- 2. Rough When all under slab plumbing is complete
- 3. Top Out and Rough Duct After all vents are out thru roof and all heating and air-conditioning ducts complete
- 4. Service Lines After gas, water, sewer lines are run to the alley (DO NOT COVER ANY LINES)
- 5. Sewer Tap After sewer is connected to city sewer main
- 6. Gas After all gas lines are installed, connect gas gauge and test all piping to a minimum of 8 PSI
- 7. Final Plumbing and Final Mechanical

ELECTRICAL PROCEDURES

- 1. Obtain Electrical Permit
- 2. Rough-in All circuits, panel, ground and feeder installed, complete and inspected before insulation and sheetrock are installed.
- 3. Underground Service Approved raceways shall be in place. Where subject to physical damage (after emergence from below grade), raceways shall consist of RMC, IMC, or Schedule 80 PVC conduit. Underground service conduits shall be buried at appropriate depths as per current NEC requirements and shall be identified by a warning ribbon above the raceway within the trench.
- 4. Electrical Final All switches, receptacles, fixtures, cooking, heating and air conditioning installed and complete. Temporary power must be connected for complete checkout of system.

BUILDING FINAL (No occupancy until building final completed)

- 1. Plans on job site
- 2. Zoning approved (Commercial)
- 3. All utilities approved
- 4. Yards cleaned and sloped
- 5. Fireplace height and flashing installed
- 6. Porch posts anchored
- 7. Insulation in and card at attic access
- 8. Bath vent operating
- 9. Kitchen hood vent shall not terminate in attic space
- 10. Smoke detectors
- 11. Sidewalks, driveways, parking area
- 12. Brick installed properly
- 13. Exits, exit lights, panic hardware

ORDER OF REQUIRED COMMERCIAL INSPECTIONS

- 2. Plumbing Rough
- 3. Return Air in Slab (if applicable)
- 4. Electrical Under Slab (if applicable)

(Item numbers 1-4 must be completed before slab inspection)

- 5. Slab Inspection
- 6. Sewer and Service Lines (water and gas)
- 7. Partial Framing (if applicable)
- 8. Plumbing Top Out
- 9. Mechanical Rough Duct (Heating and air ducts and mechanical vent ducts) Required only if sheetrock ceiling
- 10. Electrical Rough-in
- 11. Electrical Underground (if applicable)
- 12. Framing
- 13. Firewall
- 14. Gas/Plumbing Final
- 15. Electrical Final
- 16. Mechanical Final

- 17. Building Final
- 18. Irrigation Sprinkler System

NOTE: Inspections called in prior to 7:30 a.m. will be completed on the same day. Inspections called in after 7:30 a.m. will be completed the next business day. <u>NO exceptions will be made</u> unless otherwise authorized. The following contractors shall call in inspections only:

- 1. Electrical inspections-only by electrical sub-contractors
- 2. Plumbing inspections-only by plumbing sub-contractors
- 3. Mechanical inspections-only by mechanical sub-contractors
- 4. Structural inspections-only by general contractors.